Op #	Operation Descri	Equipment / Tool	Key Control Points (KCP)			
10	Apply Thermal P	Dispensing Robo	Weight Check: 2.0g ± 0.1gVisual: No gaps in coverage > 2mm			
20	Install CellsPlace	Manual Arbor Pre	Visual: Check polarity orientationTactile: Confirm audible "click" for each cell			
30	Secure BusbarPl	Electric Torque D	Torque: 5Nm ± 0.5NmVisual: Verify no cross-threading			
40	Final InspectionIr	4x Magnifying La	Visual: Pins must be parallelCleanliness: No foreign objects allowed			